

REQUEST FOR PROPOSALS

Job Site locations:

Cannon Crossing Park Tennis Courts: 1675 Nicholson Drive
Charlemagne Park Tennis Courts: 3799 Bordeaux
Hoffman Estates Illinois 60169

The Hoffman Estates Park District is requesting pricing from qualified contractors to perform the following work at Cannon Crossing and Charlemagne Parks tennis courts. All labor performed on the site by the successful contractor shall be paid in conformance with the Illinois Prevailing Wage. A certified payroll will be required prior to invoicing for work. In addition, the successful contractor will be required to provide insurance documents naming Hoffman Estates Park District as certificate holder on the policy. Insurance minimum requirements are available upon request.

Final payment will be made based on unit pricing of items installed and accepted by the district. For the basis of this proposal, estimated quantities of work have been provided so as to reflect the overall scope intent of the project. In some cases the Park District reserves the right to eliminate certain items and replace those eliminated items with other items bid as part of this proposal.

This work to begin by mid- April 2018 and be completed by May 8, 2018.

Item 1 Tennis Court fence post removal and re-installation Cannon Crossings

Contractor to remove 17 each - 10 foot high fence posts identified on map on the existing tennis court. Remove all existing concrete from posts identified to be re-placed and discard material appropriately. (Contractor may need to remove fabric so as not to damage fabric in removal process. Contractor may elect to replace existing fence posts with new fence posts to match existing instead of removing concrete from existing posts. Contractor to re-install and stretch existing fabric.) Contractor to excavate and flare post holes to a depth of no less than 42" below finish grade. Contractor to supply, place and set posts in 6 bag concrete according to industry standards. Contractor to stretch fence fabric and clean-up all waste materials and dispose of them properly.

17 posts to be re-set X \$ _____ = total \$ _____

Item 2 Tennis Court fence post removal and re-installation Charlemagne Park

Contractor to remove 4 each - 10 foot high fence posts identified on map on the existing tennis court. Remove all existing concrete from posts identified to be re-placed and discard material appropriately. (Contractor may need to remove fabric so as not to damage fabric in removal process. Contractor may elect to replace existing fence posts with new fence posts to match existing instead of removing concrete from existing posts. Contractor to re-install and stretch existing fabric) Contractor to excavate and flare post holes to a depth of no less than 42" below finish grade. Contractor to supply, place and set posts in 6 bag concrete according to industry standards. Contractor to stretch fence fabric and clean-up all waste materials and dispose of them properly.

4 posts to be re-set X \$ _____ = total \$ _____

TOTAL COST OF FENCE WORK ITEMS 1-2 \$ _____

Contractors Company name _____

Address _____

Contact Person _____

Telephone # _____

Please submit proposal by April 9, 2018 to pkusmierski@heparks.org. Question on this bid please contact Gary Buczkowski, Director of Planning and Development at 847-561-2172 or GBuczkowski@heparks.org